BANGALORE DIVISION.

Dated 24th September 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 20th October 1913 inclusive for constructing buildings for an Anglo-Vernacular School for boys at Malleswaram, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing buildings for an Anglo-Vernacular School for boys at Malleswaram, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per*	*Quantity.*
1. Earthwork excavation and filling basement ...	C. yd.	164
1*a*. Metal concrete	C. ft.	1,165
1*b*. Burnt stone in mortar	"	4,079
2. Burnt brick in mortar	"	6,465
3. Do archwork	"	84
4. Burnt stone slabs dressed	S. ft.	998
5. Teakwcod windows with iron bars, panelled outside, glazed inside, etc., complete.	"	647
6. Teakwood pannelled door with iron fastenings, etc., complete.	"	450
7. Teakwood glazed circular ventilators	"	'19
8. Rolled steel beams with painting	Cwt.	39
9. Cut stone pillars with bases, etc., capitals complete	No.	14
10. Teakwood work, wrought and put up complete ...	C. ft.	348·13
11. Pukka terrace 9"	Sq.	12·38
12. Cornice 9"	R. ft.	149
13. Brick in mortar parapets wall with pillasters cornice, etc., complete.	"	149
14. Roofing with 1st class Mangalore tiles, teak reepers, etc., complete.	Sq.	38·27
15. Ridge tiles set in mortar, etc.	R. ft.	150
16. Teakwood, eave board	"	497
17. Chunam plastering	Sq.	137·97
18. White and color washing	"	137·97
19. Flooring with 1st class 9" square Mangalore tiles over 3" concrete and cement pointing.	"	26·57
20. Flooring with Cuddapah slabs over 3" concrete and cement pointing.	"	4·80
21. Silicate painting	"	35·94
22. Wood oiling	"	25·00
23. Zinc sheets for valleys	S. ft.	53
24. Zinc down pipes	Lump sum	
25. Teakwood planting ½" thick below zinc sheet ...	S. ft.	52
26. Chunam borders	R. ft.	132
27. Teakwood finials	No.	6
28. Do pendants	"	14
29. Moulding over doors and windows	Lump sum	
30. Clearing site and levelling ground, etc. ...	"	

Dated 24th September 1913.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 20th October 1913, inclusive, for constructing buildings for a school for girls in the Malleswaram Extension of Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing buildings for a school for girls in the Malleswaram Extension of Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work	*Per*	*Quantity*
1. Earthwork excavation and filling in basement	C. yd.	130
2. Metal concrete	C. ft.	931
3. Burnt stone in mortar	"	3,204
4. Burnt brick in mortar	"	5,434
5. Do arch work	"	84
6. Burnt stone slabs, dressed	S. ft.	765
7. Teakwood panelled doors with iron fastening, etc.	"	330
8. Teakwood windows with iron bars, panelled outside, glazed inside, etc., complete.	"	472
9. Teakwood circular ventilators	"	19
10. Rolled steel beams with painting	Cwt.	19·5
11. Cut stone pillars with caps, bases, etc.	No.	8
12. Teakwood work, complete	C. ft.	281·41
13. Pukka terrace	Sqr.	6·17
14. Cornice 9"	R. ft.	72
15. Parapet wall with pillasters, cornice, etc.	"	72
16. Roofing with 1st class Mangalore tiles, teak reepers, etc.	Sq.	35·79
17. Ridge tiles set in mortar	R. ft.	150
18. Chunam plastering	Sq.	114·70
19. Teakwood eave board	R. ft.	460
20. White and colorwashing	Sq.	114·70
21. Flooring with 1st class 9" square Mangalore tiles over 3" concrete and cement pointing.	"	21·17
22. Flooring with Cuddapah slabs over 3" concrete and cement pointing.	"	3·07
23. Silicate painting	"	27·68
24. Wood oiling	"	20·00
25. Zinc sheet for valleys	S. ft.	53
26. Zinc down pipes	Lump Sum	
27. Teakwood planking ½" thick	S. ft.	52
28. Chunam borders	R. ft.	132
29. Teakwood finials	No.	6
30. Do pendants	"	14
31. Moulding over doors and windows	Lump Sum	
32. Clearing site, etc.	"	
33. Approach roads, etc.	"	

J. E. A. D'CRUZ.
Executive Engineer.